
VOYAGE PUMP STATION IMPROVEMENTS

LINCOLN CITY, OREGON

VOYAGE	PUMP STATION DESIGN DATA
PUMP STATION	
LOCATION:	NORTHERN AREA OF CITY EAST OF ROADS END
TYPE:	DUPLEX SUBMERSIBLE
PUMP TYPE:	CONSTANT SPEED, CENTRIFUGAL NON-CLOG
CAPACITY/ OPERATION POINT:	EST. 285 GPM AT 57 FT TDH EACH PUMP
PUMP HP (EACH):	7.2 HP
LEVEL CONTROL TYPE:	PRIMARY-PRESSURE TRANSDUCER, SECONDARY-LIQUID LEVEL SENSOR
OVERFLOW POINT:	PROPOSED WET WELL HATCH, EL=133.5'
OVERFLOW DISCHARGE:	DOWN GRADIENT TO WOODED NATURAL AREA
FEMA 100-YR FLOOD ELV.	N/A
TIME TO OVERFLOW:	166 MIN. AT 12 GPM AVERAGE FLOW RATE FROM PUMP ON LEVEL
AUXILIARY POWER TYPE:	CITY DIESEL GENERATOR, PORTABLE, BROUGHT TO SITE
LOCATION:	RECEPTACLE ON SITE AT EX. CONDO BUILDING, NORTH OF PUMP STATION
OUTPUT:	VARIABLE KW TO SUIT PS, 60 A PLUG
FUEL TANK CAPACITY:	CITY WILL REFILL AS NEEDED TO RUN PORTABLE EG CONTINUOUSLY
TRANSFER SWITCH:	MANUAL
ALARM TELEMETRY TYPE:	CELLULAR NETWORK COMMUNICATION
EPA RELIABILITY CLASS:	1
FORCE MAIN	
EXISTING LENGTH, TYPE:	594 LF PVC, 6-INCH
PROPOSED LENGTH, TYPE:	615 LF PVC, 6-INCH
VELOCITY AT NEW PUMPING RATE:	3.2 FT/SEC AT EST. 285 GPM FLOW RATE
PROFILE:	CONTINUOUSLY ASCENDING
DISCHARGE MANHOLE (EXIST):	EX. MANHOLE EAST OF PUMP STATION, MANHOLE #12 IN NE VOYAGE AVE.
AIR RELEASE VALVES:	NONE
VACUUM RELEASE VALVES:	NONE
AVERAGE DETENTION AT NEW PUMPING RATE:	3.3 MIN. AT EST. 285 GPM FLOW RATE
SULFIDE CONTROL SYSTEM:	NONE





INDEX TO DRAWINGS


SHT	DWG	DESCRIPTION
1	CO	TITLE SHEET
2	C1	EXISTING CONDITIONS & DEMOLITION PLAN
3	C2	PUMP STATION SITE PLAN
4	C3	PUMP STATION PLAN & SECTION
5	C4	DETAILS
6	E0	ELECTRICAL LEGEND
7	E1	ELECTRICAL ONE-LINE DIAGRAM
8	E2	ELECTRICAL LAYOUT
9	E 3	ENCLOSURE DETAIL
10	E4	WIRING DIAGRAM INCOMING POWER
11	E5	WIRING DIAGRAM POWER CONTROLS
12	E6	WIRING DIAGRAM PUMP CONTROLS
13	E7	ANALOG WIRING DIAGRAM WET WELL CONTROLS
14	E8	WIRING DIAGRAM FLOAT BACK-UP CONTROLS
15	E9	WIRING DIAGRAM ALARM CONTROLS




- 1. CITY MUST PRE-APPROVE ANY SIGNIFICANT DEVIATION FROM THESE DEQ-APPROVED CONSTRUCTION PLANS.
- 2. ALL WORK SHALL BE IN ACCORDANCE WITH THE CURRENT VERSIONS OF THE OREGON STANDARD SPECIFICATIONS FOR CONSTRUCTION (OSS) AND OREGON STANDARD DRAWINGS (OSD) PUBLISHED JOINTLY BY ODOT AND OREGON CHAPTER OF AMERICAN PUBLIC WORKS ASSOCIATION, AND ALL APPLICABLE LINCOLN CITY "MATERIALS AND CONSTRUCTION STANDARDS" AND THE MUNICIPAL CODE OF ORDINANCES. THE CITY ENGINEER WILL DETERMINE ANY PROJECT-SPECIFIC REQUIREMENTS THAT MAY DEVIATE FROM THE REFERENCED STANDARDS IF APPLICABLE AND DETERMINE THE ORDER OF PRECEDENCE IN THE CASE OF CONFLICTING REQUIREMENTS. UNLESS OTHERWISE DIRECTED, THE MORE STRINGENT REQUIREMENT WILL CONTROL.
- 3. CONTRACTOR SHALL CALL UTILITY NOTIFICATION CENTER (811) PRIOR TO CONSTRUCTION.
- 4. NO WORK SHALL BE CONDUCTED DURING WEEKENDS OR OUTSIDE OF NORMAL CITY WORK HOURS, UNLESS PRIOR PERMISSION IS OBTAINED.
- 5. CONTRACTOR SHALL PROVIDE 48 HOUR NOTIFICATION TO THE CITY PUBLIC WORKS DEPARTMENT PROJECT MANAGER OR DESIGNEE PRIOR TO THE START OF CONSTRUCTION.
- 6. SEE TOPOGRAPHIC SURVEY OF SITE FOR HORIZONTAL AND VERTICAL DATUM INFORMATION.
- 7. IF REQUIRED, CONSTRUCTION SURVEY STAKING SHALL BE PROVIDED BY THE CONTRACTOR
- 8. CONTRACTOR IS RESPONSIBLE FOR PROVIDING ACCURATE AS-BUILT RECORD OF INSTALLED WORK AND FOUND CONDITIONS AT THE END OF CONSTRUCTION.
- 9. LOCATION OF EXISTING UTILITIES AND CONDUITS IS APPROXIMATE ONLY. THE CONTRACTOR SHALL FIELD LOCATE (POTHOLE IF NEEDED) AND VERIFY EXISTING LOCATION AND DEPTH OF ALL UTILITIES AND CONDUITS BEFORE EXCAVATION WORK. CONTRACTOR WILL BE HELD FULLY LIABLE FOR ANY DAMAGE REPAIR TO EXISTING UNDERGROUND FACILITIES.
- 10. THE CONTRACTOR SHALL THOROUGHLY REVIEW THESE DOCUMENTS FOR CONFLICTS WITH EXISTING AND PROPOSED NEW UTILITIES. NOTIFY THE CITY IMMEDIATELY OF ANY POTENTIAL CONFLICTS. NEITHER THE CITY OR THE CITY'S REPRESENTATIVES/DESIGN CONSULTANTS SHALL BE RESPONSIBLE FOR ADDITIONAL CONSTRUCTION COSTS/DELAYS ASSOCIATED WITH POTENTIAL CONFLICTS THAT ARE REFLECTED ON THESE
- 11. CONTRACTOR SHALL REPORT ALL DAMAGE TO EXISTING FACILITIES IMMEDIATELY TO THE CITY.
- 12. THE LIMITS OF CONSTRUCTION SHALL BE THE PUMP STATION AREA OR AS DIRECTED BY THE CITY. ALL DISTURBED AREAS SHALL BE RESEEDED OR RESTORED ACCORDING TO PLANS OR SPECIFICATIONS. MAINTAIN ADEQUATE EROSION AND SEDIMENT CONTROL MEASURES IN PLACE UNTIL DISTURBED AREAS ARE STABILIZED TO PREVENT EROSION.
- 13. AT THE END OF EACH WORKDAY, THE CONTRACTOR SHALL CLEAN THE PROJECT AREA AND LEAVE IT IN A NEAT AND SECURED MANNER. UPON COMPLETION, THE CONTRACTOR SHALL LEAVE THE PROJECT AREA FREE OF DEBRIS AND UNUSED MATERIAL.
- 14. THE CONTRACTOR SHALL PRUNE ALL VEGETATION WITHIN THE PUMP STATION SITE AS NECESSARY AWAY AND UP FROM WORK AREA AND PERFORM ANY ROOT REMOVAL AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL PROTECT ALL EXISTING LANDSCAPING THAT IS TO REMAIN.
- 15. CONTRACTOR SHALL NOTIFY OTHER PUBLIC UTILITIES (GAS, PHONE, ELECTRIC, CABLE TV) TO MAKE ALL NECESSARY ADJUSTMENTS TO RESPECTIVE FACILITIES ALL AT CONTRACTOR EXPENSE.
- 16. THE TERM "CITY" OR "OWNER" SHALL MEAN THE CITY OF LINCOLN CITY, PUBLIC WORKS DEPARTMENT. "ENGINEER" SHALL MEAN THE CITY ENGINEER OR PUBLIC WORKS DIRECTOR OR THEIR DESIGNATED REPRESENTATIVE.
- 17. NOTICE TO EXCAVATORS: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER. THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS (503) 232-1987.

Know what's below. Call before you dig. DRAWN:

HECKED: DATE: AUGUST 16, 201





1. BURY BOTTOM OF FILTER FABRIC 6" MIN. VERTICALLY BELOW GRADE. 2. 2" x 2" FIR, PINE, OR STEEL FENCE POSTS.

3. STITCHED LOOPS TO BE INSTALLED UPHILL SIDE OF SLOPE. 4. COMPACT NATIVE FILL IN ALL AREAS OF FILTER FABRIC TRENCH.

SEDIMENT FENCE

SCALE: NONE

EROSION PREVENTION & SEDIMENT CONTROL STANDARD NOTES

- 1. CITY MUST PRE-APPROVE ANY MAJOR DEVIATION FROM THIS PLAN.
- 2. INSTALL SILT FENCE AROUND LOWER SIDES OF EXISTING PUMP STATION, EXISTING MANHOLES AND NEW CONSTRUCTION AREA. CONTRACTOR SHALL KEEP THE STREET CLEAN FROM DIRT AND DEBRIS DURING CONSTRUCTION ACTIVITIES
- 3. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN PLACE AND IN WORKING CONDITION PRIOR TO ANY LAND DISTURBING ACTIVITY INCLUDING CLEARING OR GRADING. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE APPROVED BY THE CITY EROSION SPECIALIST PRIOR TO THE COMMENCEMENT OF WORK. AN ON-SITE INSPECTION SHALL BE REQUESTED WHEN EROSION AND SEDIMENT CONTROL MEASURES ARE IN PLACE AND PRIOR TO COMMENCEMENT OF WORK. ONCE APPROVED, THE SITE MUST BI MAINTAINED THROUGH THE LIFE OF THE PROJECT, AS SHOWN ON THE PLANS.
- 4. PRIOR TO ANY SITE EXCAVATION, ALL STORM DRAIN INLETS SHALL BE PROTECTED DOWN SLOPE FROM ANY DISTURBED OR CONSTRUCTION AREAS TO PREVENT SEDIMENT FROM ENTERING THE STORM DRAINAGE SYSTEM PRIOR TO PERMANENT STABILIZATION OF THE DISTURBED AREAS. CLEAN FILTER FABRIC AS NECESSARY TO MAINTAIN DRAINAGE. REMOVE FILTER AND CLEAN CATCH BASINS FOLLOWING COMPLETION OF SITE WORK.
- 5. NEWLY CONSTRUCTED OR MODIFIED INLETS AND CATCH BASINS SHALL BE PROTECTED FROM SEDIMENT IMMEDIATELY UPON INSTALLATION.
- 6. THE CONTRACTOR SHALL NOT ALLOW SEDIMENT OR DEBRIS TO ENTER NEW OR EXISTING PIPES, CATCH BASINS OR INFILTRATION SYSTEMS. IF THIS OCCURS, THE CONTRACTOR SHALL REMOVE ALL ACCUMULATED SEDIMENT FROM THE CATCH BASINS AND STORM PIPES IMMEDIATELY. FINAL ACCEPTANCE WILL NOT BE ISSUED BY THE CITY UNTIL THIS OCCURS.
- 7. ALL EXPOSED AND UNWORKED SOILS SHALL BE STABILIZED BY THE APPROPRIATE BEST MANAGEMENT PRACTICES (BMPS). FROM OCTOBER 1 TO APRIL 30, NO SOILS SHALL BE EXPOSED AND UNWORKED FOR MORE THAN TWO (2) DAYS. FROM MAY 1 TO SEPTEMBER 30, NO SOILS SHALL BE EXPOSED AND UNWORKED FOR MORE THAN SEVEN (7) DAYS.
- 8. SOIL STOCKPILES SHALL BE STABILIZED FROM EROSION, PROTECTED WITH SEDIMENT TRAPPING MEASURES, AND WHEN POSSIBLE, BE LOCATED AWAY FROM STORM DRAIN INLETS, WATER WAYS AND DRAINAGE
- 9. IF THE BMPS APPLIED TO A SITE ARE INSUFFICIENT TO PREVENT SEDIMENT FROM REACHING WATER BODIES, ADJACENT PROPERTIES, STORM FACILITIES OR PUBLIC RIGHT-OF-WAY, THEN THE CITY SHALL REQUIRE ADDITIONAL BMPS.
- 10. IF THE CITY INSPECTOR OR ENGINEER(S) HAS EVIDENCE OF POOR CONSTRUCTION PRACTICES OR IMPROPER EROSION PREVENTION BMPS, CITATIONS AND/OR A STOP WORK ORDER SHALL BE ISSUED UNTIL PROPER MEASURES HAVE BEEN TAKEN AND APPROVED BY THE CITY OF LINCOLN CITY.
- 11. PAVEMENT SWEEPING AND SHOVELING IS REQUIRED. WASHING THE PAVEMENT INTO THE STORM SYSTEM IS NOT PERMITTED.
- 12. IF SEDIMENT, MUD OR DEBRIS IS TRANSPORTED ONTO A PAVED SURFACE OR ROADWAY, THE PAVED SURFACE OR ROADWAY SHALL BE THOROUGHLY CLEANED WITH HIGH EFFICIENCY STREET SWEEPERS AT THE END OF EACH WORKDAY, OR MORE OFTEN IF NECESSARY. SIGNIFICANT SOIL DEPOSITS SHALL BE REMOVED FROM ROADS BY SHOVELING AND SWEEPING. STREET WASHING IS NOT ALLOWED UNLESS APPROVED BY THE ENGINEER AND ONLY AFTER SEDIMENT IS REMOVED IN THE MANNER DESCRIBED ABOVE.
- 13. INSTALL SEDIMENT FENCE PER PLAN PRIOR TO CONSTRUCTION AND/OR EXCAVATION TO PREVENT SILT INTRUSION INTO R/W AND PERVIOUS CONCRETE SIDEWALK.
- 14. PERMEABLE PAVEMENT AREAS SHALL BE PROTECTED FROM SEDIMENT DURING AND AFTER INSTALLATION.
- 15. ALL EROSION PREVENTION AND SEDIMENT CONTROL BMPS SHALL BE REGULARLY INSPECTED AND MAINTAINED TO ENSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION.
- 16. THE CONTRACTOR SHALL MAINTAIN AND HAVE ON-SITE A WRITTEN LOG OF EROSION PREVENTION AND SEDIMENT CONTROL BMP MAINTENANCE.
- 17. ALL TEMPORARY EROSION PREVENTION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER SITE STABILIZATION IS ACHIEVED OR AFTER TEMPORARY BMPS ARE NO LONGER NEEDED. TRAPPED SEDIMENT SHALL BE REMOVED OR STABILIZED ON SITE. DISTURBED SOIL AREAS RESULTING FROM REMOVAL SHALL BE PERMANENTLY STABILIZED PER PLAN.

Engineering + Environmental 1500 D Street

Vancouver, WA 98663

360.690.4331



EXPIRES: 12/31/17


0

PROJECT: DRAWN:

HECKED: DATE: AUGUST 16, 201

WG NO.

SHEET NO



FLOW MANAGEMENT NOTES:

CONSTRUCT NEW VALVE VAULT, NEW BYPASS PUMPING PORT, AND NEW FORCE MAIN CONNECTION TO EXISTING FORCE MAIN. MAINTAIN EXISTING PUMP STATION IN NORMAL OPERATION UNDER EXISTING POWER SUPPLY. CONNECTION TO EXISTING FORCE MAIN SHALL BE TAPPING SLEEVE/VALVE, FORCE MAIN REMAINING IN SERVICE.

CONSTRUCT TEMPORARY FLOW MANAGEMENT SYSTEM INCLUDING MOBILE POWER AND PUMP UNIT CONNECTION TO BYPASS PORT SUMP ON OR NEAR EXISTING 8" SANITARY SEWER. AFTER PHASE 1 WORK ACCEPTED BY CITY, INSTALL TEMPORARY PLUG ON SUMP OUTLET AND PUMP TO BYPASS PORT AROUND EXISTING PUMP STATION. DISCHARGE PIPE VALVES IN VALVE VAULT TO BE CLOSED TO ALLOW TEMPORARY PUMPING THROUGH NEW FORCE MAIN / EXISTING FORCE MAIN TO OFFSITE GRAVITY MANHOLE. AUTOMATIC CONTROLS ON PUMPING REQUIRED. NOISE SILENCER ON POWER UNIT TO BE HOSPITAL GRADE. SHUTDOWN EXISTING PUMP STATION AND PLUG EXISTING FORCE MAIN OUTSIDE WET WELL.


PHASE 3

CONSTRUCTION NEW PUMP STATION/WET WELL AND ELECTRICAL IMPROVEMENTS COMPLETE, TESTED AND ACCEPTED BY CITY.

DECOMMISSION TEMPORARY FLOW MANAGEMENT SYSTEM AND REMOVE FROM SITE. NEW PUMP STATION FULLY OPERATIONAL. COMPLETE SITE RESTORATION.

TEMPORARY FLOW BYPASS PLAN

SCALE: NTS



CONCRETE MAINTENANCE PAD SCALE: NTS

GENERAL CONSTRUCTION NOTES

- 1. CONTRACTOR SHALL FIELD VERIFY THE LOCATION, ALIGNMENT, DEPTH AND INVERTS OF ALL EXISTING UTILITIES, INCLUDING EXISTING FORCE MAIN, UNDERGROUND POWER CONDUIT, UNDERGROUND EMERGENCY GENERATOR CONDUIT, OTHER EXISTING ELECTRICAL CONDUITS AND WATER SERVICE PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION.
- 2. NOTIFY CITY IMMEDIATELY OF EXISTING UTILITY CONFLICTS WITH NEW CONSTRUCTION
- 3. NO GEOTECHNICAL INVESTIGATION HAS BEEN PERFORMED. CONTRACTOR SHALL MAKE OWN DETERMINATION OF EXISTING CONDITIONS. PROVIDE SHORING AT EXCAVATION PER OSHA REQUIREMENTS. PROVIDE DEWATERING, IF NECESSARY.
- 4. SECURE THE SITE WITH FENCING TO PROTECT THE PUBLIC DURING CONSTRUCTION.
- 5. TEMPORARY FLOW BYPASS REQUIRED, PROVIDE DETAIL WORK PLAN FOR CITY APPROVAL PRIOR TO CONSTRUCTION.

CONSTRUCTION KEYNOTES

- (1) CONSTRUCT 6' PRECAST CONCRETE WET WELL EXTENSION AND CONCRETE COVER WITH ACCESS HATCH.
- 2 CONSTRUCT 7' X 7' NOMINAL PRECAST CONCRETE VALVE VAULT WITH ACCESS
- 3 CONSTRUCT DUPLEX FLYGT SUBMERSIBLE PUMP STATION IN EXISTING WET WELL, COORDINATE WITH TEMPORARY FLOW MANAGEMENT, SEE SHEET C3.
- (4) CONSTRUCT 6" FORCE MAIN CONNECTION TO EX. 6" FORCE MAIN, PVC C900 DR18, DI FITTINGS, RESTRAIN ALL FLEXIBLE/MECHANICAL JOINTS. LOCATE TO AVOID EXISTING UNDERGROUND POWER/EG AND OTHER UNDERGROUND FACILITIES TO
- (5) CONNECT NEW 6" FORCE MAIN TO EXISTING 6" FORCE MAIN WITH TAPPING SLEEVE AND GATE VALVE. COORDINATE WITH TEMPORARY FLOW MANAGEMENT.
- (6) PROVIDE SEDIMENT BARRIER FOR EROSION CONTROL, SEDIMENT FENCE OR EQUAL.
- (7) CONSTRUCT NEW ELECTRICAL CONTROL PANEL, STARTER AND RELOCATE EX. MANUAL TRANSFER SWITCH, SEE ELECTRICAL PLAN.
- (8) CONSTRUCT PVC SCH 40 SLEEVES FOR PUMP CABLES AND CONTROLS CABLES FROM PUMP STATION TO CONTROL PANEL. SIZE AND QUANTITY AS REQUIRED.
- 9 RELOCATED EX. POWER SERVICE ENTRANCE, METER AND DISCONNECT BREAKER. SEE ELECTRICAL PLAN.
- 10 CONSTRUCT 4" THICK CONCRETE MAINTENANCE PAD AT ELECTRICAL PANELS. SEE DETAIL, THIS SHEET.
- REVISE AND ENLARGE EXISTING SCREENING FACILITY TO SHIELD RESIDENT VIEW OF PUMP STATION. CONSTRUCT SIMILAR TO EXISTING AND PAINT. APPROX. 32 LF INCLUDING 8' DOUBLE GATE.
- (12) CONSTRUCT CRUSHED ROCK SURFACE AROUND PUMP STATION, VALVE VAULT AND MAINTENANCE PAD. PROVIDE 3/4"-0, 3" MIN. COMPACTED DEPTH. EXTEND AT LEAST 4' IN ALL DIRECTION AROUND PUMP STATION STRUCTURES.

GENERAL CONSTRUCTION SEQUENCE

- 1. HOLD PRE-CONSTRUCTION MEETING WITH CITY.
- 2. LOCATE EXISTING FORCE MAIN, CONDUITS AND OTHER UTILITIES.
- PROVIDE FLOW BYPASS PLAN TO CITY FOR APPROVAL.
- 4. PROTECT IN PLACE EXISTING PUMP STATION, FORCE MAIN AND APPURTENANCES UNLESS FLOW BYPASS HAS BEEN FULLY
- 5. CONSTRUCT NEW VALVE VAULT FORCE MAIN AND ELECTRICAL SYSTEMS TO EXTENT POSSIBLE WITH EXISTING PUMP STATION IN
- 6. CONNECT NEW FORCE MAIN TO EXISTING FORCE MAIN USING TAPPING SLEEVE AND GATE VALVE.
- 7. PERFORM TESTING AND INSPECTIONS ON NEW VALVE VAULT AND FORCE MAIN COMPONENTS PER CITY REQUIREMENTS.

PHASE 2

8. INSTALL FLOW BYPASS FOR TEMPORARY FLOW MANAGEMENT. IT SHALL BE EQUAL TO EXISTING PUMP STATION PEAK FLOW RATE OF 260 GPM AT 54 TDH UNLESS OTHERWISE APPROVED BY CITY. SET TEMPORARY SUMP ON OR NEAR EXISTING INFLUENT SEWER. CONNECT DISCHARGE OF FLOW BYPASS TO NEW 4" BYPASS FLANGE.

PHASE 3

- 9. DEMOLISH EXISTING PUMP STATION DRY WELL AND EXISTING WET WELL FILLET. CLEAN EXISTING WET WELL AND INSTALL NEW WET WELL EXTENSION AND COVER.
- 10. INSTALL NEW DUPLEX PUMP STATION IN EXISTING AND EXTENDED WET WELL AND REMAINING PUMP STATION IMPROVEMENTS.
- 11. PERFORM TESTING AND INSPECTIONS ON NEW PUMP STATION IMPROVEMENTS PER CITY REQUIREMENTS.
- 12. PLACE NEW PUMP STATION IN SERVICE.
- 13. COORDINATE WITH THE CITY FOR PUNCH LIST ITEMS.

PHASE 4

- 14. REMOVE TEMPORARY FLOW MANAGEMENT SYSTEM AND COMPLETE SITE RESTORATION WORK.
- SEQUENCING SHOWN IS SUGGESTED GENERAL APPROACH TO WORK. CONTRACTOR SHALL PROVIDE DETAILED PROJECT SCHEDULE AND PROPOSED WORK PLAN THAT ADDRESS THE PROJECT WORK AND THE GENERAL CONSTRUCTION SEQUENCE. ALTERNATE CONSTRUCTION SEQUENCE OR APPROACH ACCEPTABLE WITH PRIOR CITY APPROVAL.

Engineering + Environmental 1500 D Street



EXPIRES: 12/31/17

PROJECT: DRAWN:

HECKED: DATE: AUGUST 16, 201 SHEET NO

WG NO.

SCALE: NTS

GENERAL NOTES


- 1. DESIGN BASED ON FLYGT PUMP.
- 2. PROVIDE 316 SST KELLUM GRIPS FOR ALL WET WELL CABLES (5 \pm FOR: 1 EACH PUMP, FLOAT SWITCH, PRESSURE TRANSDUCER).
- 3. PLACE ALL CONDUIT IN SEALED PENETRATION THROUGH CONCRETE.
- 4. PROVIDE GUIDE RAIL SUPPORTS ATTACHED TO VERTICAL DISCHARGE PIPE AND TO EXISTING WET WELL AS SHOWN.
- 5. WET WELL, VALVE VAULT, AND HATCH SIZES ARE NOMINAL. PROVIDE DETAILED SHOP DRAWINGS SHOWING PROPOSED MATERIAL TO BE INCORPORATED INTO THE WORK.
- 6. DUCTILE IRON PIPE SHALL BE CLASS 50.
- 7. ALL MJ FITTINGS SHALL BE PROVIDED WITH MECHANICAL RESTRAINT. "MEGA-LUG" OR EQUAL.

CONSTRUCTION KEY NOTES

- PRECAST CONCRETE, 72" INSIDE DIAMETER WET WELL EXTENSION. CONCRETE COVER WITH ACCESS HATCH. WET WELL EXTENSION SHALL MATCH DIAMETER OF EXISTING 72" WET WELL, HEIGHT 5'-6" (INCLUDE COVER). ACCESS HATCH OPENING SHALL BE 3'X4' (NOMINAL) WITH 300 PSF LOADING SINGLE OR DUAL LEAF SPRING ASSISTED DOORS WITH RECESSED HANDLE. FINISH SHALL BE ALUMINUM WITH NON-SLIP TREATMENT ON DOOR EXTERIOR WITH LOCKING ASSEMBLY. CITY WILL PROVIDE PADLOCK. PROVIDE SAFETY GRATE COORDINATED WITH DOOR
- (2) 7' X 7' X 5'-6" +/- TALL (NOMINAL) PRECAST VALVE VAULT. ACCESS HATCH OPENING SHALL BE 3'X4' (NOMINAL) WITH 300 PSF LOADING SINGLE OR DUAL LEAF SPRING ASSISTED DOORS WITH RECESSED HANDLE. FINISH SHALL BE ALUMINUM WITH NON-SLIP TREATMENT ON DOOR EXTERIOR WITH LOCKING ASSEMBLY. CITY WILL PROVIDE PADLOCK. PROVIDE SAFETY GRATE COORDINATED WITH DOOR OPENING.
- SUBMERSIBLE SEWAGE PUMP ASSEMBLY MOUNTED IN FRP TOP LINER. FLYGT MODEL NP-3102.830 4" VOLUTE PUMP EQUIPPED WITH A 230 VOLT/3 PHASE/60 HZ 7.2 HP 1750 RPM MOTOR, 489 HIGH CHROME IMPELLER WITH STAINLESS STEEL GUIDE RAIL SYSTEMS, FLS LEAKAGE DETECTOR AND SUBMERSIBLE CABLES.
- (4) 4" DI DISCHARGE PIPE, FLG, LENGTH AS REQUIRED, VERIFY CONNECTION TO PUMP DISCHARGE.
- (5) 4" DI MJ SLEEVE, RESTRAINED.
- (6) 4" DI PIPE SPOOL FLG X PE, LENGTH AS REQUIRED.
- (7) 4" FLOW THROUGH PRESSURE GAUGE WITH ISOLATION VALVE, FLG
- (8) 4" SWING CHECK VALVE, FLG X FLG.
- (9) 4" PLUG VALVE, FLG X FLG.
- (10) 4" DI 45° BEND, FLG X FLG
- (11) 4" DI WYE, FLG X FLG.
- (12) GALVANIZED PIPE SUPPORT, 3 EA.
- WALL PENETRATION, SEAL WATERTIGHT SEE SHEET C5
- (14) 4" DI PIPE PE X PE, LENGTH AS REQUIRED.
- 6" X 4" DI INCREASER, MJ X MJ, RESTRAINED.
- 6" PVC PIPE, C900 DR18, LENGTH AS REQUIRED.
- 6" DI 90° BEND, MJ X MJ, RESTRAINED.
- 6" PVC PIPE, C900 DR18, CONNECT TO EXISTING FORCE MAIN, MAINTAIN LEVEL OR UPWARD SLOPE.
- (19) 4" DI SPOOL, FLG X FLG, LENGTH AS REQUIRED TO ALIGN PARALLEL PIPE RUN IN VALVE VAULT WITH PUMP DISCHARGE PIPING IN WET WELL.
- 20 4" DI SPOOL, FLG X FLG, LENGTH AS REQUIRED.
- (21) 4" DI 90° BEND, FLG X FLG.
- (22) 4" DI BLIND FLANGE FOR PUMP BYPASS/FORCE MAIN DRAIN PORT.
- 23) PROVIDE 6' COIL OF PVC FORCE MAIN "GREEN" COATING TRACER WIRE IN VALVE VAULT.
- 24 PUMP DISCHARGE PIPE SUPPORT, SEE SHEET X.
- 3" ABS DRAIN FROM VALVE VAULT.
- 4" STAINLESS STEEL FLOOR DRAIN AND GRATE.
- (27) DUCK BILL CHECK VALVE.
- 28 WET WELL VENT.
- (29) CONDUIT S FOR ELECTRICAL AND CONTROL CABLES, AS REQUIRED.
- 30 CONCRETE PAD, 4" THICK.
- INSTALL FRP LINER WITH PUMPS PER FLYGT TOP STATION INSTRUCTION. WORK WILL INCLUDE REMOVAL OF EXISTING CONCRETE FILLET, INSTALLATION OF WALL BRACKETS AND PLACEMENT OF CONCRETE UNDER AND AROUND LINER (NO VIBRATION ALLOWED).

Engineering +

Environmental 1500 D Street Vancouver, WA 98663 360.690.4331 www.pbsenv.com



EXPIRES: 12/31/17


∀ ⊢

0

MP

PROJECT: DRAWN:

HECKED: DATE: AUGUST 16, 201



PRE-CONSTRUCTION CONDITION OF ANY AND ALL AREAS DISTURBED BY


1. LANDSCAPE RESTORATION SHALL INCLUDE RESTORATION TO

2. SEED MIX: LINCOLN MIX FROM RQ MILLS (ACE) HARDWARE IN LINCOLN CITY (A FESCUE, RYE MIX) OR APPROVED EQUAL.

LANDSCAPING RESTORATION DETAIL


SCALE: NTS


CONSTRUCTION.




GRAVEL RESTORATION DETAIL

SCALE: NTS








CITY OF LINCOLN CITY VALVE BOX AND OPERATOR EXTENSION ASSEMBLY

7. FOR BUTTERFLY VALVES, MODIFICATION OF VC 212 MAY BE NECESSARY TO ENSURE THAT

THE VALVE NUT IS CENTERED IN BOX & THAT THE RISER ASSEMBLY IS VERTICALLY PLUMB.

CITY OF LINCOLN CITY TYPICAL TRENCH DETAIL

LINCOLN CITY PUBLIC WORKS DEPARTMENT AT (541) 996-2154.






TABLE C-PIPE STANCHION DIAMETER

(SCHEDULE 40 STEEL)


PIPE SIZE

NOMINAL PIPE

STANCHION DIA.

NOMINAL PIPE

STANCHION DIA.



9 PROJECT: 70970.000 DRAWN:

M 0

Engineering +

Environmental

1500 D Street

Vancouver, WA 98663

360.690.4331

www.pbsenv.com

13475

OREGON

EXPIRES: 12/31/17

0

Ē


George Drake

HECKED: DATE:

AUGUST 16, 201 SHEET NO BILL OF MATERIALS

TAG	DESCRIPTION	CATALOG NUMER	MANUFACTURER
1	CONTACTOR	A26N1-30-10-84	ABB
2	ELECTRIC OVERLOAD RESET	DR25-A-24	ABB
3	CIRCUIT BREAKER ACCESSERY	KT3VD-M	ABB
4	PISTOL HANDLE	□HB80L6	ABB
5	SHAFT	<pre>DXP6X430</pre>	ABB
6	CIRCUIT BREAKER 30 AMP	T1N030TL	ABB
7	CIRCUIT BREAKER 60 AMP	T1N060TL	ABB
8	OVERLOAD RELAY	TA250U19	ABB
9	PUSHBUTTON	800-AR2D1	ALLEN BRADLEY
10	PUSHBUTTON	800H-AR2D2	ALLEN BRADLEY
11	SWITCH	800H-JR2A	ALLEN BRADLEY
12	FLOAT SWITCH	1046376	PRIMEX
13	PWR DISTRIBUTION BLOCK, 3 POLE	67543	FERRAZ
14	PWR DISTRIBUTION BLOCK, 1 POLE	67541	FERRAZ
15	FUSE BLOCK	N2CC3I	FERRAZ
16	MOISTURE RELAY	14-40 71 13	FLYGT
17	FLOAT PAK CONTROLLER	962004-013	PRIMEX
18	ENCLOSURE	A483612SSLP	HOFFMAN
19	BACK PANEL	A48P36	HOFFMAN
20	PUMP CONTROLLER	LSC MICRO-VPAC IIT	PRIMEX
21	TIMER	GTSY-4SN6A100	IDEC
22	POWER SUPPLY	PS5R-SD24	IDEC
23	RELAY	RU4S-C-A119	IDEC
24	RELAY	RU4S-C-D24	IDEC
25	GFCI RECEPTACLE	7599-1	LE∨ITON
26	TERMINAL FUSE BLOCK	3004171	PHOENIX CONTACT
27	TERMINAL	3044102	PHOENIX CONTACT
28	IS BARRIER	5202B2	PR ELECTRONICS
29	INTRUSION SWITCH	2507A-L	SENTROL
30	TRANSFORMER	9070TF50D23	SQUARE D
31	CIRCUIT BREAKER	Q□U110	SQUARE D
32	SURGE ARRESTOR	SDSA3650	SQUARE D
33	VOLTAGE MONITOR	460	SYMCOM
34	UPS	BVUPS24PFA	TRANSTRONICS
35	BATTERY	WKA12-12F2	WERKER
36	ULTRA SONIC TRANSDUCER	dBi-10010000001-H	PULSAR
37	1.5 Kva TRANSFORMER	GENERIC	GENERIC
38	ELECTRIC HEATER	DAH1001A	HOFFMAN
39	STARTER PANEL	A302410SSLP_W/PANEL	HOFFMAN
40	WIRELESS MONIORING SYSTEM	MODEL M803 W/ COMM 16 ANT.	MISSION COMM.

	DRAWING LIST
EO	ELECTRICAL LEGEND
E1	ELECTRICAL ONE-LINE DIAGRAM
E2	ELECTRICAL LAYOUT
E3	ENCLOSURE DETAIL
E4	WIRING DIAGRAM - INCOMING POWER
E 5	WIRING DIAGRAM - POWER CONTROLS
E6	WIRING DIAGRAM - PUMP CONTROLS
E7	WIRING DIAGRAM - WET WELL CONTROLS
E8	WIRING DIAGRAM - FLOAT BACK-UP CONTROLS
E9	WIRING DIAGRAM - ALARM CONTROLS



EVERGREEN ENGINEERING

Engineering and Construction Services EUGENE, OREGON

www.evergreenengineering.com

ABBREVIATIONS

ABOVE FINISHED FLOOR TRANSFER SWITCH, AUTOMATIC CONDUIT CIRCUIT BREAKER CURRENT TRANSFORMER EXISTING GROUND FAULT INTERRUPTER HORSEPOWER JUNCTION BOX MINIMUM CIRCUIT BREAKER TRANSFER SWITCH, MANUAL NORMALLY OPEN NORMALLY CLOSED **OVERLOAD** PHASE PRIMARY

UNLESS OTHERWISE NOTED

WEATHERPROOF EXPLOSIONPROOF

POWER SYMBOLS

RECEPTACLE, 120V DUPLEX +18" AFF

POWER POLE

MAGNETIC CONTACTOR

TRANSFORMER

DISCONNECT, NON-FUSED

DISCONNECT, FUSED

ELECTRICAL CONNECTION, SINGLE MOTOR

ELECTRICAL DISTRIBUTION PANEL, SURFACE

MISCELLANEOUS PANEL, SURFACE

ELECTRICAL BASEBOARD HEATER (WATTAGE NOTED)

RECEPTACLE (ALENA 4xOR HOSEDOWN) 20AMP RATED 3 PH 3 WIRE

PLUG RATED 3 PH 3 WIRE

CONTACT NORMALLY OPEN

CONTACT NORMALLY CLOSED

GROUND

 \mathcal{L}

 $\sim\sim$

CIRCUIT BREAKER

ONE-LINE SYMBOLS

TRANSFORMER

CONNECTION POINT

THERMAL OVERLOAD

CONTROL RELAY COIL

TIMING DEVICE

SWITCH NORMALLY OPEN

MOTOR STARTER

SWITCH NORMALLY CLOSED

DIGITAL OUTPUT

ANALOG INPUT

DIGITAL INPUT

TERMINAL BLOCK (FIELD MOUNTED) 400

FUSE

人 T.C.

LIQUID LEVEL SWITCH NORMALLY OPEN CLOSE ON RISE

RESISTOR 250 OHM


> CONTACT TIME DELAY NORMALLY OPEN

ON DELAY




 Λ

DISTRIBUTION BLOCK



CIRCUIT BREAKER 3-WIRE

August 16 2016



Digitally signed by John S Shafer Date: 2016.09.01 09:32:13 -07'00'


Engineering + Environmental

1500 D Street Vancouver, WA 98663 360.690.4331 www.pbsenv.com

END <u>5</u> PUMP ELECTRIC



ISSUED FOR CON	IFC W/REVISIONS	IFC W/REVISIONS			
0	1	2			
JEC	CT:			320	5
WN	:			DI	٨
CKI	ED:			J	S
E:			:	2/15	1
3 NO	Ο.		SHI	EET	N
	- /		1		



Engineering and Construction Services
EUGENE, OREGON

www.evergreenengineering.com


PBS

Engineering +
Environmental
1500 D Street
Vancouver, WA 98663
360.690.4331

www.pbsenv.com

GENERAL NOTES:

A. ONLY ONE MOTOR WILL BE RUN AT A TIME.



			LOAD	LOA	LOAD	LOAD	CKT	-
			LOAD	LUA	LOND	LOAD	OKI	
				L1	L2	L3		
NO	CIRCUIT DESCRIP	TION	kVA	Α	Α	Α	BKR	
1	7.2 hp motor			0 20.0			50/3	
	-,			0	20.0			
	-			0		20.0		
2	7.2 hp motor			0 20.0	_		50/3	
	-1			0	20.0			
	-			0		20.0		L
3	Transformer			0 6.3			10/2	L
	-			0	6.3			L
		CONNECTED LOAD		0 46.3		40.0		L
		TOTAL kVA		0 kVA	_			L
		TOTAL AMPS PHASE		33.3				L
	1	TOTAL AMPS PHASE		33.3	Α		L	
					_			
		TOTAL AMPS PHASE	L3			27.0	Α	L
			L3	33.25 AMP	S		A	
VOLTS	120/230 1ph	TOTAL AMPS PHASE	L3	33.25 AMP	5		A	
1 20 1111	120/230 1ph	TOTAL AMPS PHASE MAX AMPS	L3	33.25 AMP	5		A	
SIZE	1.5KVA	TOTAL AMPS PHASE MAX AMPS	L3	33.25 AMP	8		A	
SIZE MAIN BREAKER		TOTAL AMPS PHASE MAX AMPS	L3	33.25 AMP	S		A	
SIZE	1.5KVA	TOTAL AMPS PHASE MAX AMPS	: L3			27.0	A	
SIZE MAIN BREAKER	1.5KVA	TOTAL AMPS PHASE MAX AMPS	L3	33.25 AMP			A	
SIZE MAIN BREAKER	1.5KVA	TOTAL AMPS PHASE MAX AMPS	: L3	LOA	D LOAD	27.0	A	
SIZE MAIN BREAKER 10 AIC SYM	1.5KVA 20 amps at 120x2	TOTAL AMPS PHASE MAX AMPS	LOAD	LOA L1	D LOAD	27.0		
SIZE MAIN BREAKER 10 AIC SYM NO	1.5KVA 20 amps at 120x2 CIRCUIT DESCRIP Heater	TOTAL AMPS PHASE MAX AMPS TION	LOAD KVA	LOA L1 A	D LOAD	27.0 CKT BKR		
SIZE MAIN BREAKER 10 AIC SYM NO 1	1.5KVA 20 amps at 120x2 CIRCUIT DESCRIP	TOTAL AMPS PHASE MAX AMPS TION	LOAD kVA 0.0	LOA L1 A	D LOAD L2 A	27.0 CKT BKR 20/1		
SIZE MAIN BREAKER 10 AIC SYM NO 1	1.5KVA 20 amps at 120x2 CIRCUIT DESCRIP Heater	TOTAL AMPS PHASE MAX AMPS TION	LOAD kVA 0.0	LOA L1 A	D LOAD L2 A	27.0 CKT BKR 20/1		
SIZE MAIN BREAKER 10 AIC SYM NO 1	1.5KVA 20 amps at 120x2 CIRCUIT DESCRIP Heater	TOTAL AMPS PHASE MAX AMPS TION	LOAD kVA 0.0	LOA L1 A	D LOAD L2 A	27.0 CKT BKR 20/1		
SIZE MAIN BREAKER 10 AIC SYM NO 1	1.5KVA 20 amps at 120x2 CIRCUIT DESCRIP Heater	TOTAL AMPS PHASE MAX AMPS TION	LOAD kVA 0.0	LOA L1 A	D LOAD L2 A	27.0 CKT BKR 20/1		
SIZE MAIN BREAKER 10 AIC SYM NO 1	1.5KVA 20 amps at 120x2 CIRCUIT DESCRIP Heater	TOTAL AMPS PHASE MAX AMPS TION	LOAD KVA 0.0 0.0	LOA L1 A 0.8	D LOAD L2 A 2.5	27.0 CKT BKR 20/1		

LOAD SUMMARY

PANEL SCHEDULI


230 3ph

MAIN BREAKER 60 AMPS 10 AIC SYM VOYAGE PUMP STATION
IMPROVEMENTS
ELECTRICAL ONE-LINE
DIAGRAM

City of City of City of City City 801 SW HWY 101 LINCOLN CITY, OR. 97367

СНК	JSS	JSS			
DATE	RHG 8/15/16 JSS	RHG 8/16/16 JSS			
ВУ	RHG	RHG			
REVISION	ISSUED FOR CONSTRUCTION	IFC W/REVISIONS			
NO.	0	1			
PR	OJEC	CT:		320	5.0

ISSUED FOR
CONSTRUCTION
WITH REVISIONS
August 16 2016



Digitally signed by John S Shafer Date:
2016.08.16
15:49:53 -07'00'

PROJECT: 3205.0

DRAWN: ADP

CHECKED: JSS

DATE: 1/25/16


DWG NO. 2


OF

10

553205.0 PBSEngr-VoyagePumpStationElect\9-Dwgs\Elec\3205-0 E1 One-line-Rev1.dwg Aug 16, 2016 03:34pm rgree

NONE





Engineering and Construction Services EUGENE, OREGON

www.evergreenengineering.com

NOTES:

- A. ALL CONDUITS SHALL BE ROUTED UNDERGROUND PER NEC, NFPA 820, AND LOCAL CODES FOR THE APPLICATION.
- B. ALL CONDUIT LOCATIONS SHALL BE COORDINATED WITH EQUIPMENT SUPPLIERS PRIOR TO INSTALLATION.
- C. CONDUITS FROM THE WET WELL SHALL BE PROPERLY SEALED TO MAINTAIN AN UNCLASSIFIED RATING AT THE EXTERIOR ENCLOSURE.
- D. SEE 33 09 10 ELECTRICAL SPECIFICATIONS FOR CONTROL PANEL DESIGN AND PROGRAMMING REQUIREMENT
- E. 2 POWER METERS ARE PRESENT AT SITE. COORDINATE WITH UTILITY WHICH METER IS TO STAY AND HOW TO DISPOSITION THE 2ND METER.

Engineering + Environmental


1500 D Street Vancouver, WA 98663 360.690.4331 www.pbsenv.com

PUMP STATION OVEMENTS LAYOUT ELECTRICAL VOYAGE





ISSUED FOR CONSTRUCTION



Digitally signed by John S Shafer DATE: Date: 2016.08.16


1/25/16 SHEET NO. 15:38:06 -07'00'


Engineering and Construction Services EUGENE, OREGON

www.evergreenengineering.com

NOTES:

- A. ALL CONDUITS SHALL BE ROUTED UNDERGROUND PER NEC, NFPA 820, AND LOCAL CODES FOR THE APPLICATION.
- B. ALL CONDUIT LOCATIONS SHALL BE COORDINATED WITH EQUIPMENT SUPPLIERS PRIOR TO INSTALLATION.
- C. CONDUITS FROM THE WET WELL SHALL BE PROPERLY SEALED TO MAINTAIN AN UNCLASSIFIED RATING AT THE EXTERIOR ENCLOSURE.
- D. SEE 33 09 10 ELECTRICAL SPECIFICATIONS FOR CONTROL PANEL DESIGN AND PROGRAMMING REQUIREMENT





NAMEPLATE SCHEDULE

SIZE

1x4

1x4

1x4

1x4

1x4

1.5x8

1x3

DESCRIPTION

BACKUP RESET

PUMP 1

PUMP 2

HAND-OFF-AUTO


OVERTEMP RESET, OVERLOAD RESET

VOYAGE PUMP


STATION

MAIN POWER

QUANTITY



CONTROL PANEL LAYOUT 3"=1'-0"



ISSUED FOR CONSTRUCTION WITH REVISIONS September 01 2016



Digitally signed by John S Shafer Date: 2016.09.01 09:33:00 -07'00'

DETAIL OVEMEN ENCLOSURE

Engineering +

Environmental


1500 D Street Vancouver, WA 98663 360.690.4331

www.pbsenv.com


CHK	JSS	JSS			
DATE	RHG 8/15/16 JSS	RHG 9/1/16 JSS			
ВУ	RHG	RHG			
REVISION	ISSUED FOR CONSTRUCTION	IFC W/REVISIONS			
NO.	0	-			
PR	OJEC	CT:		320	5.0

2/15/16 SHEET NO.

NOTES:
1. ENCLOSURE IS A NEMA TYPE 4X HOFFMAN STAINLESS.
2. UL 508A, UL 698A.




SCALE



2/15/16

SHEET NO.

EXPIRES: 06/30/2018



Engineering and Construction Services
EUGENE, OREGON

www.evergreenengineering.com

PBS

Engineering +
Environmental
1500 D Street
Vancouver, WA 98663
360.690.4331
www.pbsenv.com

VOYAGE PUMP STATION IMPROVEMENTS WIRING DIAGRAM POWER CONTROLS


City of Survey City of Eincoln City 801 SW HWY 101

LINCOLN CITY, OR. 97367

(541) 996-2151 FAX (541) 994-4881



ISSUED FOR CONSTRUCTION



Digitally signed by John S Shafer Date: 2016.08.16 15:41:26 -07'00'

DRAWN: DMT


CHECKED: JSS


DATE: 2/15/16

DWG NO. SHEET NO. 6

OF

10





Engineering and Construction Services EUGENE, OREGON

www.evergreenengineering.com

Engineering + Environmental 1500 D Street Vancouver, WA 98663 360.690.4331 www.pbsenv.com

YAGE PUMP STATION
IMPROVEMENTS
WIRING DIAGRAM
PUMP CONTROLS

3205.0


2/15/16

SHEET NO.

PROJECT: CHECKED:

DWG NO. **E6**

STERED PROFESSON 17911PE Digitally signed by John S Shafer DATE: Date: OREGON JOHN S. SHAFER 2016.08.16 15:43:23 -07'00' EXPIRES: 06/30/2018



*PROVIDED BY OTHERS

24V+

MS100

OVERLOAD RESET

PB100

PUMP 1 SS100 OFF

00X

X00

_____OOX

CR103

CR102

0L100

OVERTEMP

RESET

PB101

TO PUMP 1

1-2

3 24V+

151

157 CR605 158 CR502 159 OL100 16

CR605 161 CR100

163

164

165

166

167

(28) SF100

FLYGT MINICAS

168

1-2

CR503

CR102 155

COM

CR1Ø1 A14

0L100 97 | 98 | 8

PUMP 1 CALL

PUMP 1 RUNNING

PUMP 1 OVERLOAD RESETTABLE COIL

PUMP 1 MOTOR STARTER

PUMP 1 HOA IN AUTO

PUMP 1 RUNNING

PUMP 1 SEAL FAILURE

PUMP 1 OVERTEMP

PUMP 1 OVERLOAD

NO 101-15

NC 101-27

NC 101-24

PUMP 1 HIGH MOTOR TEMP RELAY

PUMP 1 SEAL FAILURE RELAY

IN5

-(CR1Ø2)-

A15

-CR1Ø3

A15

COM

NO 101-6, 101-7, 101-8

NO 101-22, 106-18

NO 101-16

ISSUED FOR

CONSTRUCTION

LSC J1 A1 WET WELL LEVEL

A2 STATION FLOW

EVERGREEN ENGINEERING

Engineering and Construction Services EUGENE, OREGON


www.evergreenengineering.com

KEYED NOTES:

1. WIRES MEASURED BY CT ON SHEET 4

Engineering +

Environmental 1500 D Street Vancouver, WA 98663 360.690.4331 www.pbsenv.com



2/15/16

SHEET NO.

ISSUED FOR CONSTRUCTION

STERED PROFESSION 17911PE

EXPIRES: 06/30/2018

*PROVIDED BY OTHERS

24V+ 3

1-2 3 24V+


24VDC

ULTRASONIC TRANSDUCER

INTRINSICALLY SAFE WIRE ZONE

OVDC

Digitally signed by John S Shafer Date: 2016.08.16 15:44:10 -07'00'



www.pbsenv.com


JANUARY, 2016 SHEET NO.

E8

2016.08.16

EXPIRES: 06/30/2018

15:44:58 -07'00'



Engineering and Construction Services EUGENE, OREGON

www.evergreenengineering.com


Engineering + Environmental 1500 D Street Vancouver, WA 98663 360.690.4331 www.pbsenv.com

AGE PUMP STATION
IMPROVEMENTS
WIRING DIAGRAM
ALARM CONTROLS


PROJECT:

Digitally signed CHECKED: by John S Shafer DATE:

2/15/16 SHEET NO.



ISSUED FOR



STERED PROFESSON INTERPORT

OREGON

JOHN S. SHAFER

EXPIRES: 06/30/2018

Date:

2016.09.01

09:33:58 -07'00'