



## LANDSCAPE

1 TREE PER 100' OF PERIMETER = 18  
 1 SHRUB PER 30' OF PERIMETER = 58  
 MET WITH EXISTING

Existing Trees: Individual trees indicated with **X**  
 grouping where indicated with total count.

**Total existing trees = 62**

Existing Shrubs: Individual shrubs indicated with **o**  
 grouping where indicated with total count.

**Total existing shrubs = 60**

All areas not covered by buildings, structures,  
 or impervious surfaces to be covered with  
 nonliving ground cover

## PARCEL 2 SITE SUMMARY

SITE AREA 98,010 SF 100%  
 BUILDING FOOTPRINT 20,065 SF 20%  
 PAVEMENT 61,597 SF 63%  
 LANDSCAPE AREA ONSITE 16,348 SF 17%  
 $20,265 / 600 = 34 + 14$  EMPLOYEES = 48 SPACES  
 40 PARKING SPACES PROVIDED