

Vicinity Map Not to Scale

BENCHMARK

ELEVATIONS AND CONTOURS ARE BASED ON LINCOLN COUNTY BENCHMARK NO. AZSE27. THE BENCHMARK IS AN ALUMINUM DISC APPROXIMATELY 190 FEET WEST OF THE INTERSECTION OF SW 50TH STREET AND SW EBB STREET. IT HAS AN ELEVATION OF 10.29 FEET ON THE NAVD88 DATUM.

NOTES:

н с 19 с

> CONTRACTOR IS RESPONSIBLE FOR VERIFYING EXISTING CONTOURS PRIOR TO CONSTRUCTION. CONTRACTOR SHALL NOTIFY PROJECT ENGINEER IMMEDIATELY IF ANY DISCREPANCIES ARE FOUND, CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT.

Ebb Street Lofts, Lots 5 - 9 Block 11, "3rd Addition to Taft", Lincoln City, Oregon

Owner - Developer :

Taft Development(Jason)6740 SW Raleighwood LanePortland, Oregon97225Phone (503) 810- 7270

Land Planning : NW Land Planning (Trisha) PO Box 1073 Goldendale, Wash. 98620 Phone (503) 330- 2019

Engineering : Tech. Engineering (John) PO Box 80483

Portland, Oregon 97280 Phone (503) 819- 6494

Building Architect : HM Group LLC (Elson Nguyen) Phone (971) 563-2067 Email : elson.hmgrouppdx@gmail.com

Site Address :

No address assigned, Tax Lots 2800, 2900, 3300, 3400, and 3500 on Tax Map 07 11 27DC, City of Lincoln City, Lincoln County, Oregon.

Total Site = 25,000 sf (0.57 acres) Total Disturbed Area = 0.54 ac. M/L

LOCATES (48 HOURS NOTICE REQUIRED)

ONE CALL SYSTEM: (503) 246-6699 (GENERAL TELEPHONE, NORTHWEST NATURAL

INDEX TO DRAWINGS

She	eet	No).	Description
Sheet	1	of	9	Cover Sheet, Vicinity Map and General Information
Sheet	2	of	9	Existing Condition Plan and San. Sewer Notes
Sheet	3	of	9	Existing Tree Species and Storm Sewer Notes
Sheet	4	of	9	Grading Plan
Sheet	5	of	9	Utilities Plan
Sheet	6	of	9	Storm Sewer Treatment Facility and Details
Sheet	7	of	9	Standard Details
Sheet	8	of	9	Erosion Control Plan
Sheet	9	of	9	Erosion Control Notes and Standard EC Details











TREE INFORMATION (NUMBERS 601 THROUGH 729 HAVE METAL ID TAGS) 501 SPUT 7", 11", 13", (2) 14" PINE 643 10" ALDER 602 22" SPRICE **850** 14" ALDER 603 25" SPRICE 651 11" ALDER

652

653

854

6655

655

658

659

660

(161

662

663

(164

665

胡湯

667

668

869

676

671

672

673

674

675

£7£

677

678

679

660

681

682

683

樹林

685

686

687

680

(190

691

692

693

604

695

086

17 PNE

13" PNE

14" FR

6" WILLOW

7" WILLOW

10" ALDER

12" ALDER

7" DECIDUOUS

11" ALDER DEAD

7 ALDER DEAD

TI" ALDER DEAD

8" ALDER DEAD

6" DECIDUOUS

6" DECIDUOUS

SPUT 15", 20" PINE

TT" PINE

11" PINE

9" PINE

TO ALDER

14" ALDER

14" ALDER

8" ALDER

14 ALDÉR

13" ALDER

13" PINE

7" HOLLY

SPUT O'. S' PINE

SPUT 6", 9" ALDER

SPUT 5". 9" ALDER

SPUT 14", 15" PINE

SPUT 12", 15" ALDER

SPUT 6", 7" WILLOW

SPUT 6", 10" WILLOW

14" ALDER DEAD

SPUT (2) 12" PINE

10" PINE DEAD

SPLIT 6", (3) 9" WILLOW

SPUT 8", 9", 11" WILLOW

SPLIT (2) 5" DECIDUOUS

6" HEHLOCK

7" ALDER DEAD

13" PINE 657 10" ALDER

504

606

606

607

608

500

610

611

813

614

615

616

617

518

619

620

621

622

623

624

625

628

627

628

629

630

631

632

633

64

\$35

638

637

63B

639

640

641

642

643

644

645

648

647

648

NOTES

13" PINE

7" PHE

13" PINE

14" PINE

14" PHIE

11" PNE

10" PHIE

15" PINE

13" PINE

12" PINE

B" PNE

10" PINE

19" PINE

12" PINE

17" PINE

13" ALDER

9" SPRUCE

15" ALDER

12° ALDER

15" ALDER

15" PINE

9 SPRUCE

11" ALDER

12 ALDER

6" HEMLOCK

7" HENLOCK

12 ALDER

19" PINE

15" ALDER

8" ALDER

8" PNE

18" ALDER

6" ALDER DEAD

9" ALDER DEAD

8" SPRUCE

30° SPRICE

SPUT 11", 13" ALDER

SPUT 12", 13" PHE

SPUT 17", 24" PINE

SPUT 12". 14" ALDER

SPLIT 10', 12", 13", 14" PINE

12" ALDER

SPUT (2) 13" PINE

SPUT (2) 11", (2) 13" PINE

\$97 P" SPRIKT MEB 18" ALDER DEAD 5" DECIDIUOUS 699 12 SPRICE 700 701 7" HOLLY 702 10" ALDER DEAD 703 21" SPRUCE 704 5 WELOW 705 10" PINE DEAD 706 28" SPRUCE 707 14" PINE 708 18" PHIE DEAD 10" PINE 709 32" SPRUCE 710 711 8" WELOW 7" ALDER DEAD 712 713 VO" SPRUCE 714 20" PINE 715 7" WELOW 13" SPRIXE 716 717 12" ALDER SPLIT 5". 5" HOLLY 718 719 DECIDIOUS CLUMP SPLIT 6". 7". ALDER DEAD 720 HALLOW CLUMP 721 13" PINE 722 DECIDUOUS CLUVP DECIDUOUS CLUMP 723 724 DECIDINOUS CLUMP SPLIT 10", 12" DECIDUOUS BASE 725 725 SPLIT 12". 20" PINE 727 T" ALDER DEAD 728 6" PHIE 730 7" HOLLY 729 6" DECIDIJOUS DEAD 11192 14" DECIDUOUS 11373 18 DECIDUOLIS 11374 12 DECIDUOUS 11375 10 DECIDUOUS SPUT 13", 14", 17" ALDER 11375 14" DECIDUOUS 11377 12" DECIDUOUS 11459 20" DECIDIJOUS 11470 13" DECIDIOUS 11471 16" DECIDUCUS 11472 9 DECIDIJOUS 11473 5" HEMOOK 11474 10" DECIDUOUS 17 FIR BROKEN 11475 DECIDUOUS CLUMP 11552 11614 SPLIT 8". 9" DECIDIOUS DEAD 11620 14" DECIDUOUS

RM = 13.01 GUTER INLET = 12.31 12" I.E. N (HE) = 10.4" 12" I.E. OUT (SW) = 10.7 (SD2) CURB INLET RM = 12.87 GUTTER INLET = 12.12 12° I.E. OUT (HW) = 10.5° (SD3) MANHOLE RM - 12.73 12" LE N (SE) = 1.3" 12" IE N NE) = 9.3" 12" LE. OUT (W) NOT VISIBLE (SDA) MANHOLE RM = 12.24 12" I.E. N (N) = 7.7" 12" IE N (E) = 7.8" 15" IE OUT (S) = 7.5" (SD12) HANHOLE 21 = 1213 12 IE IN (5) - 41 12° i.e. out (ii) = 4.2' (SO13) CONCRETE INLET 12" I.E. OUT (E) = 8.9" SD14) CURB INLET RM = 11.54 GUTER INLET = 10.85 挖 正 財 (前) = AT 12 LE OUT (1) - 81' SMP = 7.5'

(SD15) CUBB INLET RM = 11.51 GUTTER HILET = 10.80 12" I.E. IN (S) = 8.0" 17 IEN (1) - 7.5 12 IE OUT (SE) - 7.1' SMP = 6.7

STORM SEWER INFORMATION

(SOI) CUPB INLET

 12^{*} i.e. in (SE) = 8.6' 15" I.E. IB (M) = 6.0" 18" LE OUT (1) = 5.7 (SD7) CURB NLET EN = 11.85 SUTTER NLET = 11.00° 17 IE OUT (M) - 85 $SUMP = 7.4^{\circ}$ (SDB) CLARE MLET RM = 11.85 SUTTER MET = 10.95"

(SD5) CURB NLET

(SD6) WANHOLE

RH = 12.31

RM = 11.58

GUTTER MLET - TI.69

8" LE III (N) = 10.3"

12" LE OUT (S) = 121'

12" I.E. OUT (NIN) = 7.8" $SUMP = 7.1^{\circ}$

- (SOTE) CATCH BASIN RH = 10.79 18 IE H (W) = 7.9 12" LE OUT (D = 7.9"
- (SD17) DITCH INLET 10.51'RIM ROTTOM - 9.03" $12^{"} LE OUT (E) = BZ'$
- (SD18) VAULT 334 = 11.42'PIPES NOT MEASURABLE
- (SD18) WALLT NH = 11.63" PIPES NOT HEASURABLE

1) THE FIELD SURVEY FOR THIS WAP WAS COMPLETED ON APPLI, 2, 2021.

2) ELEVATIONS AND CONTOURS ARE BASED ON LINCOLN COUNTY BENCHWARK NO. AZSE27. THE BENCHWARK IS AN ALLMINUM DISC Approximately 190 feet west of the intersection of SW 50th street and SW EDB street. It has an elevation of 10.29 FEET ON THE NAVOBB DATEM.

3) THE BASIS OF BEARINGS FOR THIS SURVEY IS THE PLAT OF THRO ADDITION TO CITY OF TAFT.

4) THE RIGHT-OF-WAY WIDTHS WERE ESTABLISH USING INFORMATION FROM PLATS, RECORD SURVEYS AND THE TAX ASSESSOR'S HÌP.

5) THE EASEMENTS SHOWN ON THIS MAP ARE BASED ON THE TITLE REPORT, PREPARED BY WESTERN TITLE & ESCROW, WITH ORDER NUMBER WT0203050 AND WTH AN EFFECTIVE DATE OF NOVEMBER 4, 2020 AT 5:00 PM.

6) THE UNDERGROUND UTUITES ARE BASED ON THE WARKINGS PER LOCATE TICKET NUMBERS 21005452 AND 21005459.

(SD9)	CURB NLET RM = 11.56' GUTTER NLET = 10.96' 8" LE. N (E) = 8.4' 12" LE. OUT (N) = 5.5' SUMP = 6.3'
(SD10)	CURB INLET RUM = 11.52' GUTTER INLET = 11.21' 12' LE. IN (E) = 7.0' 12" LE. IN (S) = 5.9' 12" LE. OUT (SW) = 5.8' SUMP = 5.3'
(501)	NANHOLE RIN = 11.88" 12" LE. N. (NE) = 5.6" 12" LE. N. (S) 18" LE. OUT. (NN) FLOULINE = 2.8"







SCALE = 30 Ft/In







SCALE = 30 Ft/In















GENERAL NOTES

- SEE SPECIFICATIONS PROVIDED.
- THAN 10 BUSINESS DAYS, BEFORE COMMENCING ANY EXCAVATION.
- CITY/COUNTY/LINCOLN CITY.
- COMPLETION.
- INSTALLATION OF THE SYSTEMS,
- ITS ORIGINAL CONDITION UPON COMPLETION OF WORK.
- PERMANENT EROSION CONTROL METHODS ARE IN PLACE AND OPERATIONAL.
- MATERIALS



1. ALL CONSTRUCTION SHALL CONFORM TO THE CURRENT STANDARDS AND SPECIFICATIONS OF THE LINCOLN CITY CODES, THE UNIFORM BUILDING CODE APPENDIX, CHAPTER 33 EXCAVATION AND GRADING, AND THE AGREEMENT ALLOWING THE DEVELOPER TO CONSTRUCT PUBLIC IMPROVEMENTS.

2. THE EXCAVATOR MUST COMPLY WITH ALL PROVISIONS OF ORS 757.541 TO 757.571. INCLUDING NOTIFICATION OF ALL OWNERS OF UNDERGROUND FACILITIES AT LEAST 48 HOURS. BUT NOT MORE

3. THE CONTRACTOR IS RESPONSIBLE FOR CONTROLLING SEDIMENT TRANSPORT WITHIN THE PROJECT LIMITS, USING RECOGNIZED METHODS FOR EROSION CONTROL AS APPROVED BY THE

4. THE CONTRACTOR IS TO LEAVE THE PROJECT FREE OF DEBRIS AND UNUSED MATERIALS UPON

5. THE CONTRACTOR SHALL COORDINATE THE INSTALLATION OF THE UTILITY SYSTEMS SUCH AS POWER, TELEPHONE, GAS, CABLE TV, ETC., WITH EACH INDIVIDUAL UTILITY COMPANY, PRIOR TO FINAL

6. THE CONTRACTOR SHALL MAINTAIN AND PROTECT EXISTING PUBLIC AND PRIVATE UTILITY LINES AND OTHER PUBLIC UTILITY STRUCTURES. THE CONTRACTOR SHALL RESTORE ALL PUBLIC PROPERTY TO

7. TEMPORARY EROSION CONTROL METHODS MUST REMAIN IN PLACE AND BE MAINTAINED UNTIL

8. ALL AREAS TO RECEIVE FILL SHALL BE STRIPPED OF ALL VEGETATION AND OTHER DELETERIOUS





, *** 1. -







NOTES:

- 1. WHEN RAINFALL AND RUNOFF OCCURS, A KNOWLEDGEABLE AND EXPERIENCED PERSON IN THE PRINCIPLES, PRACTICES, INSTALLATION, AND MAINTENANCE OF EROSION AND SEDIMENT CONTROLS WHO WORKS FOR THE GENERAL CONTRACTOR MUST PROVIDE DAILY INSPECTIONS OF THE EROSION AND SEDIMENT CONTROLS AND DISCHARGE OUTFALLS.
- 2. OWNER OR DESIGNATED PERSON SHALL BE RESPONSIBLE FOR PROPER INSTALLATION AND MAINTENANCE OF ALL EROSION AND SEDIMENT CONTROL MEASURES, IN ACCORDANCE WITH CURRENT LINCOLN CITY AND STATE, AND FEDERAL REGULATIONS.
- 3. CONSTRUCTION ACTIVITIES MUST AVOID OR MINIMIZE EXCAVATION AND CREATION OF BARE GROUND FROM OCTOBER 1 THROUGH MAY 31ST EACH YEAR.
- 4. DURING WET WEATHER PERIOD, TEMPORARY STABILIZATION OF THE SITE MUST OCCUR AT THE END OF EACH WORK DAY.
- 5. ALL EXPOSED SOILS MUST BE COVERED DURING WET WEATHER PERIOD. (SEE DETAIL LCPW E&SC 150, 165) FOR FILL PILE, PRIOR TO ANY LAND DISTURBING ACTIVITIES, THE BOUNDARIES OF THE CLEARING LIMITS, VEGETATED BUFFERS, AND ANY SENSITIVE AREAS SHOWN ON THIS PLAN SHALL BE CLEARLY DELINEATED IN THE FIELD. UNLESS OTHERWISE APPROVED, NO DISTURBANCE IS PERMITTED BEYOND THE CLEARING LIMITS. THE OWNER/PERMITTEE MUST MAINTAIN THE DELINEATION FOR THE DURATION OF THE PROJECT. NOTE: VEGETATED CORRIDORS TO BE DELINEATED WITH ORANGE CONSTRUCTION FENCE OR APPROVED EQUAL.
- 6. PRIOR TO ANY LAND DISTURBING ACTIVITIES, THE BMPS THAT MUST BE INSTALLED ARE GRAVEL CONSTRUCTION ENTRANCE, PERIMETER SEDIMENT CONTROL, AND INLET PROTECTION. THESE BMPS MUST BE MAINTAINED FOR THE DURATION OF THE PROJECT.(SEE DETAIL LCPW E&SC - 110, 115, 120, 130, 135, 140, 145) SEDIMENT CONTROLS SUCH AS CHECK DAMS, MATS, WATTLES, SED FENCES MUST BE INSTALLED AND MAINTAINED ON ALL DOWN GRADIENT SIDES OF THE CONSTRUCTION SITE AT ALL TIMES DURING CONSTRUCTION. THEY MUST REMAIN IN PLACE UNTIL PERMANENT VEGETATION OR OTHER PERMANENT COVERING OF EXPOSED SOIL IS ESTABLISHED. (SEE LCPW DET - 115, 125, 150,155,160,170)
- 7. ALL ACTIVE INLETS MUST HAVE SEDIMENT CONTROLS INSTALLED AND MAINTAINED AT ALL TIMES DURING CONSTRUCTION. UNLESS OTHERWISE APPROVED, A SURFACE MOUNTED AND ATTACHABLE, U-SHAPED FILTER BAG IS REQUIRED FOR ALL CURB INLET CATCH BASINS. (SEE DETAIL LCPW E&SC - 135, 140, 145)
- 8. SIGNIFICANT AMOUNTS OF SEDIMENT THAT LEAVES THE SITE MUST BE CLEANED UP WITHIN 24 HOURS AND PLACED BACK ON THE SITE AND STABILIZED OR PROPERLY DISPOSED. THE CAUSE OF THE SEDIMENT RELEASE MUST BE FOUND AND PREVENTED FROM CAUSING A RECURRENCE OF THE DISCHARGE WITHIN THE SAME 24 HOURS. ANY IN-STREAM CLEAN UP OF SEDIMENT SHALL BE PREFORMED ACCORDING TO THE OREGON DEPARTMENT OF STATE LANDS REQUIRED TIME FRAME.
- 9. SEDIMENT MUST NOT BE INTENTIONALLY WASHED INTO STORM SEWERS, DRAINAGE WAYS, OR WATER BODIES.
- 10. SEDIMENT MUST BE REMOVED FROM BEHIND ALL SEDIMENT CONTROL MEASURES WHEN IT HAS REACHED A HEIGHT OF 1/3-RD THE BARRIER HEIGHT AND PRIOR TO THE CONTROL MEASURES REMOVAL.
- 11. CLEANING OF ALL STRUCTURES WITH SUMPS MUST OCCUR WHEN THE SEDIMENT RETENTION CAPACITY HAS BEEN REDUCED BY 50% AND AT COMPLETION OF PROJECT.
- 12. ANY USE OF TOXIC OR OTHER HAZARDOUS MATERIALS MUST INCLUDE PROPER STORAGE, APPLICATION, AND DISPOSAL.
- 13. THE PERMITTEE MUST PROPERLY MANAGE HAZARDOUS WASTES, USED OILS, CONTAMINATED SOILS, CONCRETE WASTE, SANITARY WASTE, LIQUID WASTE, OR OTHER TOXIC SUBSTANCES DISCOVERED OR GENERATED DURING CONSTRUCTION.
- 14. THE APPLICATION RATE OF FERTILIZERS USED TO REESTABLISH VEGETATION MUST FOLLOW MANUFACTURER'S RECOMMENDATIONS. NUTRIENT RELEASES FROM FERTILIZERS TO SURFACE WATERS MUST BE MINIMIZED. TIME RELEASE FERTILIZERS SHOULD BE USED AND CARE SHOULD BE MADE IN APPLICATION OF FERTILIZERS WITHIN ANY WATER WAY RIPARIAN ZONE.
- 15. IF VEGETATIVE SEED MIXES ARE SPECIFIED, SEEDING MUST TAKE PLACE NO LATER THAN SEPTEMBER 1ST; THE TYPE AND PERCENTAGES OF SEED IN THE MIX ARE AS IDENTIFIED ON THE PLANS OR AS SPECIFIED BY THE DESIGN ENGINEER.
- 16. WATERTIGHT TRUCKS MUST BE USED TO TRANSPORT SATURATED SOILS FROM THE CONSTRUCTION SITE. AN APPROVED EQUIVALENT IS TO DRAIN THE SOIL ON SITE AT A DESIGNATED LOCATION USING APPROPRIATE BMPS; SOIL MUST BE DRAINED SUFFICIENTLY FOR MINIMAL SPILLAGE.
- 17. ALL PUMPING OF SEDIMENT LADEN WATER MUST BE DISCHARGED OVER AN UNDISTURBED, PREFERABLY VEGETATED AREA, AND THROUGH A SEDIMENT CONTROL BMP (I.E. FILTER BAG).
- 18. THE ESC PLAN MUST BE KEPT ONSITE, ALL MEASURES SHOWN ON THE PLAN MUST BE INSTALLED PROPERLY TO ENSURE THAT SEDIMENT LADEN WATER DOES NOT ENTER A SURFACE WATER SYSTEM, ROADWAY, OR OTHER PROPERTIES.
- 19. THE ESC MEASURES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE MEASURES SHALL BE UPGRADED AS NEEDED TO MAINTAIN COMPLIANCE WITH ALL REGULATIONS.
- 20. WRITTEN ESC LOGS ARE SUGGESTED TO BE MAINTAINED ONSITE AND AVAILABLE TO DISTRICT INSPECTORS UPON REQUEST.
- 21. IN AREAS SUBJECT TO WIND EROSION, APPROPRIATE BMPS MUST BE USED WHICH MAY INCLUDE THE APPLICATION OF FINE WATER SPRAYING, PLASTIC SHEETING, MULCHING, OR OTHER APPROVED MEASURES.

STANDARD EROSION CONTROL NOTES FOR CONSTRUCTION SITES LESS THAN 1 ACRE

DETAIL: 100 - LCPW E&SC Standard Notes









